Sl No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
18	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (Pg:182, It.No-24.15 PWD SR:2018-19)								
	For Asphalt road	Sqm							
	1st Munikondappa layout		2.5	377.00	0.10		94.25		
	Cross Road		2.5	220.00	0.10		55.00		
	16th cross havnoor layout		2.5	113.00	0.10		28.25		
	15th cross road		2.5	194.00	0.10		48.50		
	14th havnoor road		2.5	159.00	0.10		39.75		
	13th cross		2.5	190.00	0.10		47.50		
	12th cross		2.5	193.00	0.10		48.25		
	11th cross		2.5	183.00	0.10		45.75		
	1st cross		2.5	120.00	0.10		30.00		
	2nd cross		2.5	268.00	0.10		67.00		
	3rd cross		2.5	182.00	0.10		45.50		
	Cross Roads		2.5	240.00	0.10		60.00		
	Cross Roads		2.5	200.00	0.10		50.00		
							659.75	454.74	300014.7
	TOTAL								**21873208.96**
	GST 12%								**2624785.08**
	PMC 1%								**250000.00**
	DPR 1%								**250000.00**
19	**Miscellaneous and unforseen Charges**								**2005.96**
								Total	**25000000.00**

CERTIFICATE

1 The Work spot has been inspected and the work found to be necessary

2 The Estimate is prepared as per the PWD SR 2018-19 & the Approved Data Rate

3 The Provision made in estimate are adequate and essential

4 This area comes under BBMP limits.

Asst Engineer
Ward No: 14
BBMP

Asst Executive Engineer
Bagalagunte Sub-division
BBMP

Executive Engineer
Dasarahalli-division
BBMP

ADMINISTRATIVELY SANCTIONED FOR
(Rupees ..Two Hundred Lakh Fifty Thousand only/-
Under the Head of Account 2.24.15 T & C
Registered as no EE(D.D.)/AS/232/19-20 Subject to conditions contained in Enclosed Memo No EE/DD/AS/232/19-20 Dt: 06/03/20

AE. (DASABAHA) Exe E.

ನಂ. CE/DZ/TS/180/18-19 ದಿನಾಂಕ : 22/02/19
ರೂ. 250.00 Lakhs
(Two fifty lakhs only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಲಾಗಿದೆ.

ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬ.ಬ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

IBID